

# CHEROKEE METROPOLITAN DISTRICT

6250 Palmer Park Blvd  
Colorado Springs, CO 80915  
(719) 597-5080

## PUBLIC UTILITY DESIGN AND CONSTRUCTION SPECIFICATIONS

Number: \_\_\_\_\_

Issued to: \_\_\_\_\_

Address: \_\_\_\_\_

\_\_\_\_\_

# CHEROKEE METROPOLITAN DISTRICT

6250 Palmer Park Blvd  
Colorado Springs, CO 80915  
(719) 597-5080

## PUBLIC UTILITY DESIGN AND CONSTRUCTION SPECIFICATIONS

		Date of Original Issue	Date of Latest Revision
Part I	Water System Standard Specifications		
Part II	Wastewater Collection System Standard Specifications		
Part III	Earthwork Standard Specifications		

**PART I**

**WATER SYSTEM STANDARD SPECIFICATIONS  
(Issued 07/15/19)**

**TABLE OF CONTENTS**

**CHAPTER 1 - GENERAL**

<u>Section</u>	<u>Title</u>	
1.01	Authority .....	I-1-1
1.02	Effective Date of Specifications.....	I-1-1
1.03	Revisions, Amendments or Additions .....	I-1-1
1.04	District Control.....	I-1-1
1.05	Organization and Interpretation of Specifications .....	I-1-1
1.06	Definitions .....	I-1-1
1.07	Abbreviations .....	I-1-2

**CHAPTER 2 - MAIN EXTENSIONS**

<u>Section</u>	<u>Title</u>	
2.01	Extensions Defined .....	I-2-1
2.02	Standard Specifications to Apply .....	I-2-1
2.03	Responsibility for Main Extensions.....	I-2-1
2.04	Application Procedure .....	I-2-1
2.05	Plan Requirements for Water System Extensions .....	I-2-2
2.06	Plan and Profile Drawings.....	I-2-6
2.07	Conflicts Between Plans and Specifications .....	I-2-7
2.08	Construction Procedure .....	I-2-7
2.09	Surveying .....	I-2-8
2.10	Placing Survey Lines.....	I-2-8
2.11	Notice of Field Staking and Construction by the Developer .....	I-2-8
2.12	Inspection.....	I-2-8
2.13	Performance Agreement and Bill of Sale.....	I-2-9
2.14	Special Conditions .....	I-2-10

## CHAPTER 3 - DISTRIBUTION SYSTEM DESIGN AND LAYOUT

<u>Section</u>	<u>Title</u>	
3.01	General .....	I-3-1
3.02	Quality of the Distribution System .....	I-3-1
3.03	Sizing of Distribution Mains .....	I-3-1
3.04	Fire Protection .....	I-3-1
3.05	Distribution Regulation Installations .....	I-3-2
3.06	Pumping Facilities .....	I-3-3
3.07	Storage Facilities.....	I-3-3
3.08	Layout of the Distribution System .....	I-3-3
3.09	Line Valves.....	I-3-4
3.10	Connections to Mains for Fire Sprinkler Lines.....	I-3-4
3.11	Clearance and Encasement Design for Sanitary and Storm Sewer Crossings .....	I-3-4

## CHAPTER 4 - MATERIALS

<u>Section</u>	<u>Title</u>	
4.01	Materials and Testing.....	I-4-1
4.02	Size of Mains.....	I-4-1
4.03	Distribution System Piping .....	I-4-1
4.04	Pipe Fittings .....	I-4-2
4.05	Steel Pipe and Fittings .....	I-4-3
4.06	Gate Valves.....	I-4-4
4.07	Valve Boxes .....	I-4-4
4.08	Fire Hydrants.....	I-4-5
4.09	Corrosion Protection Systems.....	I-4-6
4.10	Concrete Thrust Blocks, Anchors and Structures .....	I-4-7
4.11	Mechanical Joint Restraint .....	I-4-8
4.12	Casing Pipe.....	I-4-9
4.13	Responsibility for Materials .....	I-4-9
4.14	Handling of Materials .....	I-4-9
4.15	Pressure Regulation Valves and Accessories .....	I-4-10

## CHAPTER 5 - PIPE INSTALLATION

<u>Section</u>	<u>Title</u>	
5.01	Approval by the District .....	I-5-1
5.02	Handling of Materials .....	I-5-1
5.03	Inspection and Preparation of Pipe and Fittings .....	I-5-1
5.04	Cutting and Fitting of Pipe.....	I-5-1

## CHAPTER 5 - PIPE INSTALLATION (continued)

<u>Section</u>	<u>Title</u>	
5.05	Pipe Joint Lubrication .....	I-5-1
5.06	Pipe Alignment and Grade .....	I-5-1
5.07	Deviation from Alignment and Grade Occasioned by Other Structures .....	I-5-2
5.08	Temporary Bulkheads .....	I-5-2
5.09	Frost .....	I-5-2
5.10	Excavation, Bedding and Backfill .....	I-5-2
5.11	Lowering of Material into the Trench .....	I-5-3
5.12	Laying of Pipe .....	I-5-3
5.13	Ductile Iron Pipe .....	I-5-3
5.14	Polyvinyl Chloride Pressure Pipe .....	I-5-5
5.15	Installation of Valves .....	I-5-5
5.16	Valve Boxes .....	I-5-6
5.17	Installation of Fittings .....	I-5-6
5.18	Fire Hydrants .....	I-5-6
5.19	Dead Ends and Blow Offs .....	I-5-7
5.20	Thrust Blocks and Anchors .....	I-5-8
5.21	Vaults .....	I-5-9
5.22	Harness Rods .....	I-5-9
5.23	Bridging and Encasement of Pipe .....	I-5-9
5.24	Encasement or Sleeve Pipe .....	I-5-10
5.25	Connections to the District's System .....	I-5-10
5.26	Corrosion Protection Systems .....	I-5-11
5.27	Disinfection .....	I-5-12
5.28	Pressure Testing .....	I-5-13
5.29	Acceptance and Release for Taps .....	I-5-13
5.30	Acceptance of Mains and Service Lines Including Curb Stops .....	I-5-14
5.31	Abandonment of Existing Infrastructure .....	I-5-14

## CHAPTER 6 - SERVICE LINES

<u>Section</u>	<u>Title</u>	
6.01	All New Service Lines and, Where Applicable, Service Line Replacements .....	I-6-1
6.02	Water Service Line Excavations for All New and Replacement Service Lines .....	I-6-2
6.03	Service Line Installation and Material for All New and Replacement Service Lines .....	I-6-3
6.04	Curb Stop and Curb Box for All New and Replacement Service Lines .....	I-6-4

## CHAPTER 6 - SERVICE LINES (continued)

<u>Section</u>	<u>Title</u>	
6.05	Water Meters - General .....	I-6-5
6.06	Inside Water Meter Installations Only .....	I-6-5
6.07	Combined Domestic and Fire Line Water Meters .....	I-6-6
6.08	Water Regulators .....	I-6-6
6.09	Inspection of Services for All New and Replacement Service Lines.....	I-6-7
6.10	Repair and Replacement of Existing Service Lines .....	I-6-7
6.11	Service Line - General Notes .....	I-6-8

## CHAPTER 7 - WATER SERVICE QUALITY CONTROL REGULATIONS

<u>Section</u>	<u>Title</u>	
7.01	General .....	I-7-1
7.02	Cross Connection Control & Backflow Prevention - Criteria List .....	I-7-6

## STANDARD DRAWINGS

<u>No.</u>	<u>Title</u>
W-1	Typical Utilities Location
W-2	Typical Water Plan - District Mains
W-3	Typical Water Plan - Private Mains
W-4	Fire Hydrant Locations
W-5	Fire Hydrant Installation
W-6	Fire Hydrant Specifications
W-7	Valve Installation and Location
W-8	Valve Box Installation
W-9	Polyethylene Wrap
W-10	Bonding Joint and Anode Installation
W-11	Insulator Installation
W-12	Copper Tracer Wire on PVC Service
W-13	Thrust Block Data
W-14	Thrust Blocks Required for Taps
W-15	Typical Trench Cross Section
W-16	Maximum Pipeline Deflection Data
W-17	Pipe Cutting

## STANDARD DRAWINGS (continued)

<u>No.</u>	<u>Title</u>
W-18A	Reverse Anchor Detail
W-18B	Reverse Anchor Detail
W-19	Concrete Pipe Encasement Detail
W-20	Water Line Lowering Detail
W-21	Pipe Bridging Detail
W-22	Temporary and Permanent Blow Off Assemblies for 6" and 8" Mains
W-23	Temporary and Permanent Blow Off Assemblies for 12-inch and Larger
W-24	Blow-Off Assembly Dimension Data for 12-inch or Larger
W-25	Pipe Tapping Detail
W-26	Flange Lug Detail
W-27	Applications for Mechanical Joint Restraints
W-28	Restrained M.J. Pipe Length Data
W-29	12-Inch Check Valve Station
W-30	Pressure Relief Station
W-31	8-Inch Size Pressure Regulator Station
W-32	6-Inch Size Pressure Regulator Station
W-33	2" Air and Vacuum Valve Station
W-34	Standard Concrete Vault for Valve Installations - Precast
W-35	Water Department - Typical Utilities Location for Valve Installation - Cast-in-Place
W-36	Protecting Tie-Rods
W-37	Taping Detail - 3/4" thru 2"
W-38	Typical Service Locations to Residential Dwelling
W-38A	Alternate Service Line Trench - Common Ditch for Water or Sewer
W-39	Water Meter Loop for 3/4" thru 1" Meters
W-40	Alternate Water Meter Pit Installation
W-41	Irrigation Service 3/4" and 1" Meter Installation
W-42	1½" and 2" Irrigation Meter